



PASCHIM BANGA GRAMIN BANK  
Regional Office, Howrah.  
20/1/15Bhagawan Chatterjee Lane, Howrah 711101.

DATE- 26-08-2022

Tender Notice

Sir/Madam,

**Paschim Banga Gramin Bank, Regional Office - Howrah** invites application cum sealed quotations from authorized experience vendors for **Electrical and LAN work** as per schedule(B.O.Q) & layout (enclosed) of Bagnan Branch-new premises . Intending suppliers are requested to submit the quotation in sealed envelope at R.O HOWRAH as per below mentioned notice.

SL.NO	DESCRIPTION - 1	DESCRIPTION - 2
1	NAME & LOCATION OF WORK	Interior Furniture Work At BAGNAN BRANCH-NEW PREMISES .PASCHIM BANGA GRAMIN BANK ,BAGNAN BRANCH.BAGNAN HOWRAH 711303.
2	TIME ALLOWED FOR COMPLETION	<b>10 Days including Sundays &amp; Holidays.</b>
3	QUERIES	ON OR BEFORE 31/08/2022 IN BETWEEN 3.00PM TO 4.00 PM ON EACH DAY.CONTACT PERSON :MR.ARNAB MUKHERJEE,OMM-II,AGA ; MOB:9804923106.E-MAIL:"Howrahro.Acct" <Howrahro.Acct@Mail.Pbgb.Co.In>;
4	LAST DATE & TIME OF SUBMISSION OF TENDER DOCUMENT	<b>3 PM ON OR BEFORE - 05/09/2022</b>
5	DATE & TIME OF OPENING OF SEALED BID	<b>3.30 PM ON 05/09/2022</b>
6	ADDRESS OF SUBMISSION OF TENDER DOCUMENT	SENIOR MANAGER (AGA) PASCHIM BANGA GRAMIN BANK REGIONAL OFFICE,HOWRAH. 20/1/15Bhagawan Chatterjee Lane, Howrah 711101
7	DEFECTIVE LIABILITY REPORT	12 MONTHS FROM THE DATE OF VIRTUAL COMPLETION AT WORK.
8	VALIDITY OF OFFER	3 MONTHS FROM THE DATE OF OPENING OF PRICE BID .
9	LIQUATED DAMAGES	0.5% PER WEEK SUBJECT TO A MAXIMUM OF 5% OF CONTRACT VALUE.
10	APPROXIMATE ESTIMATED COST OF THE PROJECT	QUOTED RATE + GST AS APPLICABLE
11	DOCUMENTS REQUIRED TO BE SUBMITTED WITH QUOTATION AT PASCHIM BANGA GRAMIN BANK REGIONAL OFFICE HOWRAH	<b>ENVELOP-1(TECHNICAL BID)</b> 1.SCANNED COPY OF VALID TRADE LICENCE & P-TAX. 2.SCANNED COPY OF PAN. 3.SCANNED COPY OF ITR FOR THE FINANCIAL YEAR 2018-19,2019-20 ,2020-21 & 2021-22. 4.GST REGISTRATION NO:- RETURN OF (GSTR-1/GSTR-3) FOR LAST YEAR 2021-22. <b>ENVELOP - 2(COMMERCIAL BID/PRICE BID)</b> ENVELOP - 1 & ENVELOP - 2 -COMBINED IN BIG ENVELOP.

**PBGB-ROH Has The Right To Accept /Reject any/All Quotation(S) Without Assigning Any Reason.**

**REGIONAL MANAGER**

PASCHIM BANGA GRAMIN BANK,REGIONAL OFFICE HOWRAH  
20/1/15 BHAGABAN CHATTERJEE LANE,HOWRAH -711101

# PASCHIM BANGA GRAMIN BANK

(A GOVERNMENT ENTERPRISE)

BAGNAN BRANCH, HOWRAH

## ELECTRICAL AND LAN WORK SCHEDULE FOR PASCHIM BANGA GRAMIN BANK, BAGNAN BR

SI No	Description of the work	Unit	Qty	Rate (Rs)	Amount (Rs)
1	"Supply and installation (Concealed/Surface) of Double door 4way TPN DB with MCB having breaking capacity of 25 KA. a) incoming- 1 No ... 63mp ,25KA,4P MCB b)outgoing - 12 Nos. 10-25 Amp SP MCB C series with Necessary blanking plate as required.(As per IS8828-96Latest)" (HAVELLS/HAHAGER/LEGRAND)	Nos	1		
2	Supply & installation of 1.1 KV Grade PVC insulated and sheathed armoured AL cable with GI earth continuity wire by MS bar saddles on wall ( GLOSTER/POLYCAB) ( CESC TO main panel)				
	a) 4C x 25 sq.mm.	Mtrs	40		
3	End connection of above cable with heavy duty nickle plated brass compression gland crimping type socket insulation tape etc. with all concern.				
	a) 4C x 25 sq.mm.	Nos	2		
4	Supply and fixing of 100amp fuse cut out for WBSEDCL or CESC power connection	Nos	4		
5	Supply & installation of TPN front operated 63A, 25KA, 4P MCCB (adjustable overload and fixed short circuit) in factory fabricated, powder coat painted metal enclosure complete along with statutory caution board, earthing and having wall mounting hinges etc. The box must have sufficient space for Aluminium cable termination upto 35 sqmm.	Nos	1		
6	Supply & installation(concealed) of Double Door 8way SPN MCB DB with following accessories a)1 No. 32 amp. 100 mA DP RCBO as incomer b) 6 Nos. 6-10 Amps SP MCB Make: HAVELLS/HAGER/LEGRAND (FOR UPS DB)	Nos	1		
7	Supply & fixing 11-18 amp north-west AC starter with plugtop indicator type and socket (Havells/Hager)	Nos	4		
8	Distribution wiring(concealed/surface) including new point wiring 660 volt grade 3x1.5 sq.mm. (cu) PVC flexible wire in 20 SWG Rigid PVC (ISI Marked) conduit along with Conduit accessories circular boxes, MS boxes, 6 Amps Modular Type switch with socket outlets 6 pin, all individual control switch etc. Conduit size & nos of wires in conduit as per code of practice with circuit wiring with (2x2.5 + 1X1.5) sq.mm. copper wire from MCB DB to respective sw board. N.B. (i)Earth & neutral may be looped but from the last point earth & Neutral has to be connected with sw board. (ii)Point wiring should be inclusive of continuous wire length up to the connection block of light fittings/fans. (PVC CONDUIT: BEC /NIC/AKG. WIRE : FINOLEX/POLYCAB/HAVELLS. Switch-				
	a) Light point(one switch controls one light)	Nos	15		
	d) Exhaust fan	Nos	2		
	g) Ceiling fan point with two module regulator	Nos	8		
	h) Board plug point with 5 pin So and 6 amp switch	Nos	8		

9	Point wiring with 660 V grade PVC insulated multi strand copper wire through ISI marked minimum 2 mm thick PVC conduit with junction box ,circular box, elbows ,bends, couplers and other accessories concealed ( below the false ceiling) or by chase cutting on wall /floor or on surface by bar saddles : PVC CONDUIT: BEC /NIC/AKG/PLAZA WIRE : FINOLEX/POLYCAB/HAVELLS/MESCAB				
	a) 2X2.5 sq mm +1X1.5 sq mm in 20 mm dia conduit (For UPS and Power Sockets)	Mtrs	240		
	b) 2X4 sq mm +1X1.5 sq mm in 20 mm dia conduit (AC points & Glow sign DB)	Mtrs	80		
	c) 2X6 sq mm +1X2.5 sq mm in 20 mm dia conduit (UPS / LDB Incoming)	Mtrs	45		
10	Distribution wiring including new point wiring 660 volt grade 2x2.5+1x1.5 sq.mm. (copper ) PVC insulated flexible wire in 20 SWG Rigid PVC (ISI Marked) conduit along with Conduit accessories circular boxes, MS boxes, 2 x 6 Amps + 2 x 6 Amps modular type switch and socket (HAGER/HAVELLS)	Sets	6		
11	Distribution wiring including new point wiring 660 volt grade 2x2.5+1x1.5 sq.mm. (copper ) PVC insulated flexible wire in 20 SWG Rigid PVC (ISI Marked) conduit along with Conduit accessories circular boxes, MS boxes, 1 x 6 Amps + 1 x 6 Amps modular type switch and socket (HAGER/HAVELLS)	Sets	3		
12	"Supply & installation of MS Flush Metal box with front plate enclosing the following duly interconnected :a) 2 Nos 16 amp switch (with indicator) & 2 Nos 6 amps sockets and 1 no. 6/16 amps socket outlet b) 1 No. mounting box c) 1 No. front plate (HAGER/HAVELLS)	Sets	8		
<b>UPS ROOM</b>					
13	Supply & fixing on wall industrial Plug & socket DB in metal enclosure with one 40 Amps industrial socket (P+N+E) but with 40Amps DP MCB (Havells/Hager/Legrand)duly inter connected	Nos	2		
<b>Fans</b>					
14	Supply & Installation of 9" dia Exhaust fan 900 rpm with louver including cutting (Crompton/Bajaj) (for toilet)	Nos	2		
<b>LIGHT'S</b>					
15	Supplying and fixing of angular /batten holder with 12 Watt LED lamp (Philips/Bajaj/Havells) on wall or ceiling with necessary interconnection.	Nos	3		
<b>EARTHING</b>					
16	Earthing as per IE 3043 Rules including making of 1 No. earth station with 50 mm dia 3 mts. length GI pipe (Class B) buried at an average depth of 3 mts. below ground level with 7/14 stranded earth lead wire upto earth busbar including providing masonry inspection pit and restoration of surface duly rammed.	Nos	2		
17	S&F Tinned copper Earth Bar on insulator (25 mm x 6mm x 3mm)	Nos	1		
18	S&F 2 x 1.5 PVC Armored copper Cable for Generator Neutral, CBS, VSAT earthing (From Earth station to 16 Amp VSAT sw at system room) (Polycab/Gloster)(CONCEALED WHERE NECESSARY)	Mtrs	70		
<b>19 LAN WORK (Data /Voice Network System)</b>					
	a) Supply & Installation of cat - 6 Data Cable (D-Link)	Mtrs	200		
	b) Supply and Fixing 20/25 mm dia ISI make PVC Conduit with accessories	Mtrs	80		
	c) RJ - 45 Data Socket with plate and box (D-Link)	Nos	8		

	d) Supply & Installation of Voice Cable - 4 pair Telephone Cable un armoured PVC Sheated .	Mtrs	80		
	e) RJ - 11 (D-Link) Voice Socket with plate and box (D-Link)	Nos	3		
	f) 5 Pair Tag Block Crome type on MS box	Nos	1		
	g) Patch code - 1 Meter	Nos	8		
	h) Patch code - 2 Meter	Nos	8		
	<b>OTHER MISCELENEOUS</b>				
20	Removing & Refixing of electrical gadgets like Fan, Light with fittings, DB's, P/F 9U Rack, Port switch & Jack panel etc. (excluding AC) from Old branch to New branch.	LS			
	<b>Rupees :</b>			<b>Total</b>	
	<b>GST will be applicable extra</b>				

For PASCHIM BANGA GRAMIN BANK

Regional Manager  
Paschim Banga Gramin Bank (Brah)